

pressure must support 2500psi. Concrete in and around the area (6' x 6') of the baseplate must be free of cracks and must appear in good condition. Existing concrete must be a minimum of 6" thick reinforced with a minimum 3,000psi (5 bag mix), soil

- If the concrete conditions are not met, refer to the manufacturer's foundation requirement.
- Anchors must have an embedment of at least 5".

1-1/4" holes

14

- Customer/installer is responsible for determining the adequacy of the concrete floor and correct
- Grout is recommended under the base plate to level the mast
- 6' x 6' square area (3' perimeter) where jib is installed must be free of cracks, seams, joints, walls, and delamination.
- Jib must be professionally inspected once a month

24" BOLT CIRCLE

By signing this, the customer or installer agrees to follow the above specification. All Lift Cranes LLC is not liable if the jib crane is not properly installed.

0

0

Company representative -

Company name -



2127 W. NORDALE DR. APPLETON, WI 54914 PH - 920-380-0397 FAX - 920-380-0845

-MAXIMUM TROLLEY/HOIST WEIGHT 80LBS, -ANCHOR BOLTS AND FOUNDATION SUPPLIED BY OTHERS

M Z

ណ៍

MIN 6"