

Existing concrete must be a minimum of 6° thick reinforced with a minimum 3,000psi (5 bag mix), soil pressure must support 2500psi. Concrete in and around the area (6° x 6°) of the baseplate must be free of cracks and must appear in good condition.

- If the concrete conditions are not met, refer to the manufacturer's foundation requirement.
- Anchors must have an embedment of at least 5".

1-1/4" holes

 $\tilde{\omega}$

- Customer/installer is responsible for determining the adequacy of the concrete floor and correct anchors be used.
- Grout is recommended under the base plate to level the mast.
- 6' x 6' square area (3' perimeter) where jib is installed must be free of cracks, seams, joints, walls, and delamination.
- I'b must be professionally inspected once a month.

24" BOLT CIRCLE

By signing this, the customer or installer agrees to follow the above specification. All Lift Cranes LLC is not liable if the Jib crane is not properly installed.

Сотрапу пате - _____

0

Company representative -______



2127 W. NORDALE DR. APPLETON, WI 54914 PH - 920-380-0397 FAX - 920-380-0845



MIZ

ណ៍

MIN 6"