

of cracks and must appear in good condition. pressure must support 2500psi. Concrete in and around the area (6' x 6') of the baseplate must be free

- If the concrete conditions are not met, refer to the manufacturer's foundation requirement.
- Anchors must have an embedment of at least 5".

1-1/4" holes

ά

- Customer/installer is responsible for determining the adequacy of the concrete floor and correct
- Grout is recommended under the base plate to level the mast.
- 6' x 6' square area (3' perimeter) where jib is installed must be free of cracks, seams, joints, walls, and delamination.
- Jib must be professionally inspected once a month.

24" BOLT CIRCLE

not liable if the jib crane is not properly installed. By signing this, the customer or installer agrees to follow the above specification. All Lift Cranes LLC is

0

Company name -

Company representative -



2127 W. NORDALE DR. APPLETON, WI 54914 PH - 920-380-0397 FAX - 920-380-0845

-MAXIMUM TROLLEY/HOIST WEIGHT 80LBS. -ANCHOR BOLTS AND FOUNDATION SUPPLIED BY OTHERS

M N N

ហ្

MIN 6"